SMART WATER CONSUMPTION MONITORING SYSTEM

CHAPTERS IV AND V

Project-based manuscript draft

Calape, Bohol

Prepared from the implemented Laravel and ESP32 project

August 2026

CHAPTER IV

METHODOLOGY, SYSTEM DESIGN, AND IMPLEMENTATION

This chapter presents the development methodology, requirements, design, database structure, implementation process, and verification results of the Smart Water Consumption Monitoring System. The organization follows the academic flow of the supplied reference document, while all technical descriptions in this chapter are derived from the actual Smart Water project files, routes, database migrations, firmware, interface templates, services, and automated tests.

4.1 Requirements Analysis and Requirements Documentation

Requirements analysis identified three principal actors: the municipal administrator, the household account holder, and the commissioned smart meter. The administrator manages household records, municipal meters, water-rate configuration, billing statements, leak incidents, notifications, analytics, reports, and audit information. The household user reviews live and historical consumption, estimated billing, leak status, notifications, and account settings. The smart meter measures flow-sensor pulses and submits authenticated interval readings to the server.

4.1.1 Functional Requirements

ID	Requirement	Verified Project Behavior
FR-01	User and access management	Administrator creates and manages household accounts; public registration is restricted; account status governs access.
FR-02	Municipal device lifecycle	Register, assign, activate, rotate credentials, reassign, suspend, and decommission meters.
FR-03	Telemetry ingestion	Accept authenticated interval readings containing a stable reading identifier, flow rate, liters used, meter state, and device diagnostics.
FR-04	Consumption monitoring	Display live readings, daily/weekly/monthly history, summaries, comparisons, and availability states.
FR-05	Estimated billing	Apply the latest applicable water rate, fixed charge, subsidy, and billable consumption to estimates and monthly statements.

ID	Requirement	Verified Project Behavior
FR-06	Leak and threshold detection	Evaluate server-configured thresholds, notify affected users, and support an administrator resolution workflow.
FR-07	Notifications	Create, read, archive, retry, and remove household or administrative notices according to role and ownership.
FR-08	Reports and exports	Produce consumption, billing, leak, notification, and operational reports with filtering and export support.
FR-09	Audit and analytics	Record administrative/security activity and present household- or administrator-scoped analytics.
FR-10	Account maintenance	Allow authenticated users to update permitted profile fields and change passwords.

4.1.2 Non-Functional Requirements

Quality Attribute	System Response
Security	Laravel Sanctum tokens, role middleware, scoped device credentials, hashed one-time activation codes, token revocation, and audit redaction.
Reliability	Stable reading identifiers prevent double counting; unsent meter intervals are retained in ESP32 Preferences until acknowledged.
Performance	The meter uploads at three-second intervals and the web interface is designed to refresh live information at the same cadence.
Data integrity	Foreign keys, validation, unique identifiers, server-owned household/device associations, precision-preserving numeric fields, and historical charge snapshots.
Usability	Responsive administrator and household workspaces, accessible labels, keyboard-oriented controls, role identification, and light/dark theme support.
Maintainability	Controllers are grouped by feature; models represent domain entities; services isolate billing, analytics, consumption, and audit logic.
Portability	The web application supports SQLite or MySQL, while the field device targets ESP32-S3/M5Stack CoreS3 hardware.

4.1.3 Use-Case Description

Use Case	Actor	Precondition	Main Flow	Result
Manage household accounts	Administrator	Authenticated administrator	Create, search, filter, edit, suspend, deactivate, or archive a household account.	A role-scoped household record with a standardized account number.
Commission a smart meter	Administrator + Device	Registered and eligible household	Register the asset, issue a one-time code, activate from the ESP32, and bind the hardware identity.	Active scoped device credential and assigned meter.
Upload a reading	Smart meter	Active assigned device and valid token	Measure pulses, calculate interval values, submit JSON, validate identity, and save once.	Owned water reading and updated server total.
Review consumption	Household	Authenticated active account	Open live monitoring or history; select a period; retrieve scoped readings and summaries.	Current flow, usage totals, trends, and availability state.
Generate billing statement	Administrator	Valid rate and billable readings	Select the billing month, aggregate consumption, apply charge rules, and save a snapshot.	Finalized statement with status and balances.
Resolve a leak alert	Administrator	Leak incident exists	Review household and reading evidence, notify, classify, resolve, mark false alarm, or reopen.	Updated incident state and traceable response.

4.2 System Design, Software, and Processes

The system uses an Internet of Things client-server design. The physical meter performs measurement and short-term persistence, while the Laravel server remains authoritative for identity, ownership, cumulative usage, billing rules, threshold evaluation, and record storage. The browser interfaces consume protected JSON endpoints and present role-specific workspaces.

Figure 4.1. Smart Water Consumption Monitoring System architecture.

4.2.1 Telemetry and Billing Process

Commissioning begins in the administrator workspace. The device exchanges its UUID, expiring activation code, hardware ID, and firmware version for a scoped credential. Each reading includes a stable reading_id derived from the registered device identity and local sequence. If transmission fails, the pending interval remains stored in the device. When the API acknowledges the reading, the local sequence advances and the interval accumulator is cleared. The server validates ownership and computes authoritative totals before exposing information to users.

Figure 4.2. Device commissioning, telemetry, calculation, and user-response workflow.

4.2.2 Technology Used

Layer	Technology	Purpose
Backend	PHP 8.3+; Laravel Framework 13.8; Laravel Sanctum 4.0	Routing, validation, authentication, API controllers, services, reports, and persistence.
Frontend	Blade, JavaScript, Tailwind CSS 4, Vite 8	Responsive household and administrator workspaces, charts, filters, forms, and live refresh.
Database	SQLite or MySQL	Users, meters, readings, rates, billing statements, notifications, leak alerts, audit logs, sessions, and tokens.
Embedded device	ESP32-S3 / M5Stack CoreS3; M5Unified; Wi-Fi; HTTPClient; Preferences	Pulse measurement, device display, activation, reliable telemetry, and local pending-state storage.
Reporting	Dompdf 3.1.2 and CSV export endpoints	Printable operational reports and downloadable tabular records.
Testing	PHPUnit 12.5.12 through Laravel test runner	Feature verification for access control, telemetry, billing, alerts, analytics, devices, and interfaces.

4.3 Entity Relationship Diagram

The principal database relationships connect household users to their assigned devices, readings, statements, notifications, and leak incidents. A device may be temporarily unassigned during municipal inventory or maintenance, but an uploaded reading is tied to both the

authenticated device and its current household. Billing configuration can be municipal or user-specific, and finalized statements preserve the charge values applied at generation time.

Figure 4.3. Core entity relationship overview (operational fields summarized).

4.4 Data Dictionary

The following data dictionary summarizes the operational tables most directly involved in monitoring, billing, alerting, and administration. Framework-support tables for cache, jobs, sessions, password resets, and personal access tokens remain part of the implementation but are omitted from the main discussion for clarity.

Table	Important Fields	Purpose
users	id; name; email; role; account_number; address; phone; is_active; account_status; created_by_admin; timestamps	Household and administrator identities, contact details, and access state.
devices	id; household_id; device_uuid; asset_number; manufacturer_serial; hardware_id; firmware_version; installation_date; status; last_seen_at; activation metadata	Municipal meter registry, assignment, identity binding, health, and lifecycle.
water_readings	id; user_id; device_id; reading_id; flow_rate; liters_used; cubic_meter; estimated_bill; rate; threshold and leak flags; connectivity fields; recorded_at	Time-stamped, device-owned interval telemetry and derived monitoring state.
billings	id; user_id; water_rate; fixed_monthly_charge; subsidy_deduction; currency; effective_date; threshold_liters; leak rules; is_active	Effective-dated municipal or household billing and monitoring configuration.
billing_statements	id; user_id; billing_month; opening_balance; total_liters; total_cubic_meter; water_rate; fixed charge; subsidy; current_charge; amount_paid; remaining_balance; status	Historical monthly statement and payment-state snapshot.
notifications	id; user_id; created_by; type; title; message; read state; batch; delivery status/error; sent/scheduled/archived timestamps	Household notices, administrator announcements, delivery lifecycle, and read status.
leak_alerts	id; user_id; first/latest reading IDs; notification_id; status; detected/resolved timestamps; resolution notes; last notified date	Operational incident record supporting notification, classification, resolution, false-alarm handling, and reopening.
audit_logs	id; user_id; action; entity type/id; metadata; IP address; user agent; request ID; created_at	Trace of administrative and security-sensitive activity with contextual metadata.

4.5 Development and Testing

Development is organized around feature-specific API controllers and domain services. WaterConsumptionService and HouseholdConsumptionService handle aggregation and availability semantics; BillingStatementService preserves monthly charge logic; AnalyticsService produces range-based summaries; and the embedded firmware handles acquisition, display, activation, and delivery reliability. Verification combines automated feature tests with a production frontend build.

Verification	Coverage / Output	Status	Duration	Observation
Laravel automated test suite	181 tests; 1,178 assertions	181 passed; 0 failed	22.390 seconds	The current test run completed without failed cases.
Frontend production build	Vite 8.0.16; 4 modules transformed	Passed	6.75 seconds	CSS, boot JavaScript, main JavaScript, and manifest were produced successfully.

Current verification status: The complete automated suite passed with 181 tests and 1,178 assertions. This verifies the tested software behaviors but does not replace physical sensor calibration or field validation.

4.5.1 Major Test Areas

- Authentication and account restrictions, including blocked, suspended, archived, deleted, and unauthorized users.
- Municipal device registration, activation, hardware binding, credential rotation, reassignment, health, and decommissioning.

- Telemetry validation, device ownership, idempotent reading identifiers, server-authoritative totals, and precision.
- Household live readings, time-zone-aware periods, cumulative-reset handling, missing-data semantics, and billing estimates.
- Water-rate configuration, fixed monthly charges, statement generation, status changes, and historical billing fields.
- Leak alert creation, notification, resolution, false-alarm handling, reopening, and role protection.
- Administrator reporting, analytics, customer management, exports, notification lifecycle, and interface accessibility contracts.

4.6 Implementation Plan

Phase	Owner	Activity	Expected Output
1. Environment preparation	Municipal IT / Developers	Configure PHP, database, application key, mail/queue behavior, timezone, LAN URL, and production assets.	Environment checklist and successful health endpoint.
2. Database deployment	Developers	Back up the target database, run migrations and controlled seeders, and verify indexes and foreign keys.	Current schema and verified baseline records.
3. Administrator setup	System administrator	Create authorized staff accounts, set water rates and alert rules, and verify audit logging.	Operational administrative workspace.
4. Household onboarding	Authorized staff	Create household records with required address, contact details, role, status, and account number.	Active household accounts ready for assignment.
5. Meter commissioning	Technician + Administrator	Register each meter, record asset details, assign household, activate once, and verify last-seen health.	Bound device and successful telemetry.
6. Pilot verification	Project team	Compare measured volume with a calibrated reference, verify network recovery, review alerts, and reconcile billing estimates.	Signed pilot acceptance record.
7. Production rollout	Municipality	Deploy in phases, train staff and households, monitor audit/leak/device dashboards, and maintain backups.	Controlled operational adoption.

4.6.1 Implementation Issues and Challenges

Issue	Effect	Mitigation
Sensor calibration	Pulse-to-liter conversion varies by sensor, pipe conditions, pressure, and installation.	Perform volumetric calibration per installed meter and retain calibration records.
Network interruption	LAN or Wi-Fi loss can delay near-real-time visibility.	Use the firmware pending-reading state, stable IDs, health windows, and field connectivity checks.
Duplicate or noisy pulses	Electrical noise may inflate flow readings.	Use minimum pulse intervals, abnormal-burst rejection, and site validation.
Credential handling	Activation codes or tokens may be exposed during commissioning.	Issue short-lived single-use codes, remove codes after activation, rotate credentials, and restrict administrator access.
Billing configuration	Incorrect effective dates or rate settings can affect estimates and statements.	Require authorized review, retain charge snapshots, and reconcile pilot statements before rollout.
Automated regression verification	The current automated suite completed without failed cases.	Maintain the automated suite in continuous verification as the system evolves.

4.7 System Implementation and Results

The implemented application provides a complete path from a registered physical meter to role-scoped monitoring and administrative action. The meter reports measured intervals; the API validates device identity; the database preserves raw and derived values; services calculate consumption and estimated billing; and the user interfaces expose monitoring, leak, notification, billing, analytics, and reporting functions. The successful production asset build and 181 automated tests with 1,178 assertions passed in the current verification run, demonstrating broad functional coverage of the implemented software.

Interpretation: The implementation is suitable for continued pilot testing and controlled demonstration. Production acceptance should follow calibration, backup, security, network-recovery, official billing review, and documented field validation.

CHAPTER V

PRESENTATION, ANALYSIS, AND INTERPRETATION OF RESULTS

This chapter presents the implemented interfaces and interprets the results of the Smart Water Consumption Monitoring System against its operational objectives. The figures are structured interface maps derived from the current Blade templates and implemented navigation. They summarize the actual workspace composition without presenting fabricated household consumption values.

5.1 Landing and Authentication Interface

The public entry points provide a landing page, splash page, and login page. Authentication is API-based and uses Laravel Sanctum. Public registration is intentionally unavailable; household accounts are created by authorized administrators. Successful authentication directs the user to the workspace corresponding to the account role. The login interface includes an accessible password visibility control, while the shared page shell provides theme controls and responsive navigation.

Interface Element	Function	Interpretation
Landing page	Introduces the water-monitoring service and directs users to authentication.	Keeps public content separate from protected operational data.
Login form	Validates email and password and requests a scoped session token.	Centralizes access and blocks inactive, suspended, archived, incomplete, or unauthorized accounts.
Role redirect	Routes administrators and households to their own workspace.	Reduces accidental exposure of administrative controls.

5.2 Household Dashboard Interface

The household workspace uses a compact authenticated layout with a collapsible sidebar and recent-notification control. The dashboard summarizes current flow rate, estimated bill, leak status, meter connection, and notification count. It also provides usage comparison, meter history, latest meter activity, and recent alerts. Range controls support predefined periods and a validated custom date range.

Figure 5.1. Household workspace interface map derived from the implemented dashboard template.

5.2.1 Live Monitoring

Live Monitoring displays recent readings from the M5Stack CoreS3 device and a real-time consumption trend. Date filters and selectable row counts allow the household to narrow the displayed interval. The live state is based on the meter heartbeat rather than on a nonzero flow rate, so a connected meter can correctly report zero water use. Missing readings are not silently interpreted as zero consumption.

5.2.2 Consumption History

Consumption History groups information by daily, weekly, and monthly periods and provides summary cards, a trend chart, and detailed reading totals. The implemented consumption service distinguishes interval readings from cumulative device totals, handles safe differences when cumulative meters reset, and uses the configured application timezone when constructing reporting periods.

5.2.3 Estimated Billing

The billing interface presents a single current estimate, a transparent billing breakdown, assigned-meter information, and finalized statement history. The calculation requires valid billable readings and an applicable active rate. Current charges may include the configured rate per cubic meter, fixed monthly charge, subsidy deduction, and prior balance according to the statement logic. When inputs are unavailable, the interface presents a specific availability message rather than a misleading zero estimate.

5.2.4 Leak Detection and Notifications

Leak Detection presents the latest meter signal, configured threshold, and response status. The notification inbox contains account, billing, consumption, meter, and leak-related notices. Received notifications may be marked as read or removed from the household view without erasing the municipality's source record. This separation protects operational traceability while allowing households to manage their inbox.

5.2.5 Account Settings

Account Settings allows the household to update permitted contact information and change the password. Protected fields—including role, administrative creation state, and server-owned account controls—remain outside normal household editing. This supports self-service maintenance without weakening authorization boundaries.

5.3 Administrator Operations Interface

The administrator workspace consolidates municipal operations in one responsive shell. Its overview includes account and meter health, consumption trend, operational follow-ups, notifications, and recent administrative or device events. Global search and feature-specific filters support efficient retrieval of households, meters, billing records, incidents, reports, and notices.

Figure 5.2. Administrator workspace interface map derived from the implemented admin template.

Module	Implemented Functions	Result / Interpretation
Customer Management	Create household accounts; search by name, email, account, address, or meter; filter status; update, suspend, deactivate, archive, or unassign a meter.	Administrative account creation and explicit status controls support controlled onboarding.
Device Management	Register municipal assets, assign households, issue activation codes, review hardware/firmware/last-seen health, rotate credentials, reassign, and decommission.	The registry separates equipment inventory from interactive user accounts.
Water Rate Management	Configure rates, fixed charges, currency, effective dates, consumption thresholds, leak thresholds, durations, and notification behavior.	Effective-dated configuration supports transparent billing and monitoring rules.

Module	Implemented Functions	Result / Interpretation
Billing Management	Search estimated and finalized records, filter period/type/status, generate statements, review calculation details, and mark payments.	A preserved statement snapshot improves historical consistency.
Consumption Monitoring	Search households, filter readings, open daily/weekly/monthly history, and inspect meter state and totals.	Administrators can investigate usage without weakening household data scoping.
Leak Monitoring	Review affected household, latest flow, notice history, and resolution state; resolve, classify false alarm, or reopen.	Leak events become managed incidents instead of one-time flags.
Reports	Preview and export consumption, billing, notification, and leak reports for a selected range.	Operational data is available for municipal review and record keeping.
Notification Management	Compose official notices, select audience and category, track delivery/read status, retry, archive, and delete sent records.	Delivery lifecycle and audit information support accountable communication.

5.4 Smart Meter Interface and Field Operation

The M5Stack CoreS3 screen presents Wi-Fi status, server connection, flow rate, total liters, cubic-meter usage, and leak indication. Firmware samples pulse counts every second and attempts an upload every three seconds. It rejects very short duplicate edges and abnormal pulse bursts, retains pending readings across failures, and clears the interval only after server acknowledgement. These behaviors reduce the risk of lost or double-counted usage during temporary connectivity problems.

Device Indicator	Source	Operational Meaning
Wi-Fi status	ESP32 connection state	Whether the meter is connected to the configured local network.
Server status	Latest telemetry response	Whether the API acknowledged a recent upload.
Flow rate	Pulse count over elapsed time	Current water-flow estimate in liters per minute.
Total liters	Server total when available; otherwise device total	Running consumption display with server authority preferred.
Usage in cubic meters	Liter conversion	Consumption unit used by water-rate calculations.
Leak indication	Server response	Whether configured leak logic marked the current event as possible leakage.

5.5 Analysis of System Results

Objective	Evidence from Implementation	Status	Interpretation
Near-real-time monitoring	Three-second device upload and dashboard refresh design; precise interval fields; scoped live endpoints.	Implemented	Supports timely household and municipal visibility, subject to network availability.
Reliable device identity	Municipal registry, one-time activation, hardware binding, scoped token, and lifecycle revocation.	Implemented	Reduces unauthorized or misassigned telemetry.
Accurate record ownership	Server derives household and device from the authenticated meter and rejects invalid associations.	Implemented	Prevents clients from selecting another household for a reading.
Billing transparency	Effective rate selection, fixed charge, subsidy, statements, explanation states, and historical charge snapshot.	Implemented	Provides traceable estimates and finalized monthly records.
Leak response	Threshold evaluation, once-per-event notice behavior, incident list, follow-up, resolution, false alarm, and reopening.	Implemented	Transforms sensor conditions into an actionable workflow.
Regression acceptance	181 automated tests with 1,178 assertions passed; frontend production build passed.	Passed for tested software behaviors	Broad coverage is present. Physical calibration, field-network testing, and usability validation remain required before full deployment acceptance.

5.6 Findings

- The project implements the full information path from a commissioned flow meter to household and municipal dashboards.

- Security boundaries are explicit: administrators control household creation and municipal devices, households receive only their scoped records, and devices hold limited upload credentials.
- Data-quality handling is stronger than simple cumulative summation because stable reading identifiers, interval usage, reset-aware aggregation, and missing-data states are represented separately.
- Billing results are explainable because current estimates, active rates, fixed charges, subsidies, historical statements, and unavailable-data messages are distinct.
- Leak monitoring is operational rather than purely visual because alerts can be notified, followed up, resolved, marked false, and reopened.
- The current automated verification run passed all 181 tests and 1,178 assertions. This evidence supports software-level functional acceptance, but it does not substitute for physical sensor calibration, field-network testing, or usability validation with household users.

5.7 Conclusions

Based on the implemented project and the verification performed, the Smart Water Consumption Monitoring System meets its principal functional purpose: it captures water-flow telemetry from an ESP32-S3/M5Stack CoreS3 meter, stores device- and household-owned readings, presents near-real-time and historical consumption, produces estimated and finalized billing information, manages leak and threshold notifications, and provides municipal tools for accounts, devices, incidents, reports, and audit review. The separation of household, administrator, and device roles creates a sound access-control foundation for municipal deployment.

The system also demonstrates practical reliability measures through persistent pending readings, idempotent reading identifiers, server-authoritative totals, effective-dated billing rules, and explicit missing-data states. However, software acceptance alone is insufficient for field deployment. Sensor calibration, network recovery, physical installation, backup restoration, security review, and reconciliation with official billing procedures require documented pilot evidence. The completed automated verification supports regression readiness for the tested software behaviors.

5.8 Recommendations

Recommendation	Required Action
Maintain automated regression verification	Run the full suite after every material software change and investigate any failed case before release.
Conduct calibrated field trials	Compare measured volume against a certified reference container or meter across low, normal, and high flow, recording calibration constants and acceptable error.
Formalize acceptance criteria	Define measurable thresholds for telemetry delay, recovery after outage, billing variance, leak-detection sensitivity, false alarms, availability, and user task completion.
Strengthen production operations	Use HTTPS, secure secrets, scheduled backups, restoration drills, log retention, least-privilege accounts, patch management, and network monitoring.
Validate official billing integration	Review rates, fixed charges, subsidies, rounding, arrears, due dates, adjustments, and payment posting with the responsible municipal office.
Train users by role	Prepare short administrator, technician, and household guides covering onboarding, meter health, alert response, report generation, and account safety.
Extend notification channels carefully	After pilot validation, consider queued email or SMS delivery with consent, retry limits, delivery logs, and privacy controls.
Evaluate long-term analytics	After sufficient production data exists, review seasonal consumption, meter anomalies, leak recurrence, and conservation outcomes without inferring missing readings as zero.

5.9 Chapter Summary

Chapter V presented the user and device interfaces, analyzed the implemented modules, mapped the system results to core objectives, and identified the conditions required for deployment. The evidence supports continued pilot use and finalization, with full production acceptance dependent on calibrated field validation, operational controls, official billing review, and documented physical field validation.